



PRESSURE RATING: 50 PSI
MAX TEMP: 120 F
SERVICE FLUID: POOL SYSTEM




Duplex strainers are a good choice for critical systems for which flow interruption is prohibited. A properly designed composite duplex strainer assembly will allow full flow through one strainer, while the other is isolated and in standby with a clean basket in place. Monitoring the pressure drop via optional pressure taps on inlet/outlet manifold allows for easy identification of when basket becomes fouled and changeover is required.



PN	Strainer Size	Face to Face (inch) A	Center Line (inch) B	Width (inch) W	Height (inch) H
SW216102031	2	21 1/4	10 1/2	25 5/8	21 1/8
SW216103031	3	29 3/16	10 1/2	37 1/8	21 1/8
SW216104031	4	35 9/16	11 5/8	45 1/8	23 1/8
SW216105031	5	47 1/2	16	60 1/8	28 1/8
SW216106031	6	47 1/2	16	60 1/2	28 1/8
SW216108031	8	60 1/16	21 1/2	76 1/2	36 1/8
SW216110031	10	73 3/16	23	94 3/8	40 1/8
SW216112031	12	87 3/16	31 5/8	113 1/8	48 5/8
SW216114031	14	94 3/16	33	121	50 1/8



Designed for Fast Basket Removal



Durable Quick Release

Solid 316 SS T-Handle allows tool-less maintenance without galling or breaking.



Ergonomic

Remove the basket without bending over. All nuts, bolts, and gaskets stay attached, and the lid stores on its shelf.

Customer Committed

30+ years in Strainer Manufacturing
20 year housing Lifespan
98+% Customer Satisfaction
Immediate US Customer Support
Support parts ship next day



Strong

316 SS Baskets construction will handle worst case loading.



Dependable

Corrosive barrier bonded to non-rusting FRP housing does not require painting.





SPC-FRP-004: SPECIFICATION FOR MOLDED FIBERGLASS REINFORCED PLASTIC (FRP) BASKET STRAINERS IN POOL RECIRCULATION SYSTEM- SW DUPLEX SERIES

1. SCOPE

The molded fiberglass reinforced plastic basket strainer shall be designed for the suction side of pool recirculation systems in continuous operation. These strainers are designed for easy operation, assuming maintenance personnel have limited training and minimal tools to clean the basket. Baskets are designed to remove primarily hair and lint, in addition to other foreign objects typically found in water parks, pools, and other recreational plumbing systems. Typical installations include the suction side of the recirculation pump that operating at high flow rates and minimal pressure drops.

2. DESIGN REQUIREMENTS

2.1. Configuration

- 2.1.1. Strainer type shall be flanged basket
- 2.1.2. Effluent shall be in-line with the influent
- 2.1.3. Height, drain port, basket size, and face-face dimensions shall be interchangeable with Fluidtrol SW DUPLEX series design

2.2. Flanges

- 2.2.1. Flanges shall allow easy installation into piping system by limiting rotational nozzle stress and flange bolt hole misalignments
 - 2.2.1.1. Flanges 12" and smaller shall be ANSI 150# Van Stone type
 - 2.2.1.2. Flanges 14" and larger shall require dimensional and load verification
- 2.2.2. Flange material shall be PVC Cell Class 23447-B ASTM D-1784

2.3. Basket

- 2.3.1. Basket material shall be 316 Stainless Steel
- 2.3.2. Basket perforation shall be 1/8" on 3/16" centers
- 2.3.3. Basket shall have handle welded to body, capable of holding 50lbs of debris
- 2.3.4. Basket shall be able to withstand 15 psi pressure drop across the perforated wall
- 2.3.5. Basket open area shall be a minimum of 4 times greater than influent cross-section area

2.4. Basket Maintenance

- 2.4.1. No tools shall be required to remove the lid
- 2.4.2. The lid shall be clear acrylic lid with a minimum thickness of 1" and flexural strength greater than 15,000 psi
- 2.4.3. Lid attachment shall be with 316 Stainless Steel Tee Handles / Swing Bolts
- 2.4.4. Gasket grooves shall be in the strainer body to prevent accidental misplacement
- 2.4.5. Basket shall self-center and remove in one simple motion

- 2.4.6. Basket shall be suspended to ensure positive seal at the basket flange
- 2.4.7. Vent plugs shall allow for gas removal without lid removal
- 2.4.8. Drain plugs shall be minimum 1 inch off floor to prevent plugging from debris
- 2.5. Duplex Operation
 - 2.5.1. Two strainers shall be included, each capable of handling the system flowrate.
 - 2.5.2. Butterfly valves shall be used to allow the strainer to be isolated and cleaned. while flowing in the other strainer
 - 2.5.3. All elbows, tees, flanges, valves shall be made of SCH 80 PVC or better.
 - 2.5.4. Bolting for flanges, tees, and valves shall be SS 304 or better.
- 2.6. Operating Conditions
 - 2.6.1. Normal operating temperature is 75 deg F.
 - 2.6.2. Maximum fluid temperature shall be 140 deg F with reduced pressure rating.
 - 2.6.3. Normal operating pressure is 2 psi suction.
 - 2.6.4. Maximum operating pressure is 50 psi with no surge.
 - 2.6.5. Maximum suction pressure is 14 psig vacuum.
- 2.7. Pressure Rating
 - 2.7.1. Hydrostatic testing of strainer and components at 35 psig shall be conducted on every unit.
- 2.8. Materials of Construction
 - 2.8.1. Gaskets shall be EPDM or Silicone
 - 2.8.2. Shell shall be FRP with high grade, corrosive resistant vinyl ester resin matrix
 - 2.8.3. Strainer shall be constructed from components certified to NSF/ANSI 61
 - 2.8.4. Exterior shall have UV protective inhibitors to maximize service life
 - 2.8.5. Flanges shall be PVC Cell class 23447-B, ASTM D-1784
- 3. CONSTRUCTION
 - 3.1. Manufacturer shall have minimum five year service history in industry
 - 3.2. Manufacturer shall maintain as-built dimensions of each strainer
 - 3.3. Manufacturer shall be ISO 9001:2008 Certified
 - 3.4. Manufacturer shall supply minimum one year warranty on lids, baskets, and gaskets to cover defect in material or workmanship
 - 3.5. Manufacturer shall supply minimum five year warranty on FRP shell to cover defect in material or workmanship
 - 3.6. Approved manufacturer
 - 3.6.1. Fluidtrol Process Technologies, Inc. www.fluidtrol.com